

Crossway Church Re-Bid 5/16/11
Alternate Descriptions

Alternate #1

Reduce the Ground Floor structural slab deck and the Lower Level slab on grade patio as follows:

- Delete all Lower Level and Ground Level deck and patio construction including structural steel framing between column lines 1 to 2 and F to L
- Delete pads, piers, steel columns and CMU enclosures at F-1, G-1 and H.1-1
- Shift CMU enclosures at J-1, K-1 and L-1 to column line 2
- Delete piers, columns and CMU enclosures at F-2, G-2 and H-2
- Modify the Ground Floor level deck railing system to accommodate the deck modifications for a safe egress route to the exterior stair system
- Delete Door #112-6 and replace with a window Type W3. Include any wall framing, drywall and siding modifications

Alternate #2

Delete the entire outdoor cooking area enclosure and equipment as indicated on FS-1.1 and Elevation "B" on FS-1.2

Alternate #3

Change the jack shaft passenger elevator to a holeless hydraulic elevator to fit the same hoistway dimensions

Alternate #4

Delete tow roof dormer areas as follows:

- North Elevation between column line J and L
- South Elevation between column line J and L (louvered dormer areas must remain for HVAC air)
 - Modify the GluLam construction as required
 - Modify the wood decking as required
 - Delete the aluminum windows
 - Delete the perimeter metal wall stud framing and drywall
 - Modify the roofing, siding, gutters and downspouts